

AGATA detector tests

University of Cologne
Herbert Hess

B. Birkenbach, B. Bruyneel, J. Eberth, D. Lersch, G. Pascovici,
P. Reiter, A. Wiens
IKP Cologne

H.-G. Thomas CTT Montabaur



Experimental setup and specifications

Core FWHM

at 1.3 MeV: < 2.35 keV


at 122 keV: < 1.35 keV

Crosstalk < 0.1 %

Segments FWHM

at 1.3 MeV : < 2.30 keV, mean < 2.10 keV

at 60 keV: < 1.30 keV, mean < 1.20 keV




Test results A005 – 73949

Core: noise band did not decrease below 100mV (1500V)
leakage current increased linearly with applied HV
FWHM at 1.3 MeV: 13.07 keV at 6 μ s shaping time
11.23 keV at 3 μ s

Segments: noise band ~ 15mV
exception B6 ~ 80mV
FWHM at 1.3 MeV: B6 = 13.39keV
B3 = 2.27keV
B5 = 2.24keV
A6 = 2.03keV

-> Detector is suffering from leakage current
Confirmation of the Saclay results



-> Rejected

Test results B001 - 74034

Core FWHM at 1.3MeV : 3.26keV (6 μ s)
2.70keV (3 μ s)


Segments FWHM at 1.3MeV:

A6 = 2.62keV (6 μ s)

A6 = 1.49keV (3 μ s)

D6 = 2.72keV (6 μ s)

D6 = 1.86keV (3 μ s)



-> Detector suffers from leakage current over segments A6 and D6

-> Rejected

Test results B005 – 74065 (I)

Core


noise band increases from 150mV at 100V to 500mV at 500V
at 3 μ s shaping time noise band 300mV
very high leakage current, 20nA at 500V

Segments

noise band 15mV at 500V
exception F6 ~ 200mV (200V)

-> detector not operational – confirmation of the Saclay results

B005 : Leakagecurrent



-> Rejected

Test results B005 - 74065

Second delivery 05.03.09
in warm condition segment B6 missing

B005 in ATC3

in cold condition all segments present

Core FWHM at 60keV 1.88keV (6 μ s)
1.89keV (3 μ s)

Segments FWHM F1 at 60keV > 4keV

-> out of specification

upside down position


FWHM at 60keV: core 1.30keV
F1 1.15keV

-> within specification




-> Test ongoing

Test results C005 - 74033



Cross talk level is within specification of 0.1%



FWHM core at 122keV = 1.21keV
at 1.3MeV = 2.25keV

-> Mounted in ATC2

Status C003 - 74013

Accepted in summer 2007

mounted in ATC2(summer 2008)

->leakage current over segment **C1**

after refurbishing by Canberra
retested in winter 2008


FWHM core at 60keV = 1.32keV

1.3MeV = 2.32keV

mounted in ATC3

-> leakage current over segment **C1**

FWHM segment C1 = 1.63keV (1.08keV in Testcryostat)



-> New detector test required

Status B006 - 74076

CAT done in Saclay – detector within specification

delivery to Cologne

mounted in ATC3 -> leakage current over segment F5 and A1

results to be confirmed in test cryostat

-> New detector test required

Summary

5 detectors delivered since last AGATA week

2 detectors accepted (1 Cologne and 1 Saclay)

2 of the accepted detectors seem to have problems with leakage current

main problem is leakage current caused by a damage of the outer contact or the implantation layer